5th International SedNet Conference 27th-29th May 2008

Backfilling of the Eastport in Bremerhaven/Germany Organic Harbour Mud as Construction Material

27. May 2008

Dipl.-Ing. Dirk Lesemann, PHW mbH, Hamburg

for

Hans Nickels, Kai Petereit (PHW mbH),
Klaus Waßmuth (Heinrich Hirdes GmbH),
Christoph Tarras, Stefan Woltering (bremenports GmbH & Co.KG)







Organic Harbour Mud as Construction Material







Organic Harbour Mud as Construction Material



Initial situation


Installation of sheet pile wall


Replacement of harbour mud

Silt (O)

Clay/ Peat (O)

Sand (O)





(O): originally; (B): backfilled; (SP): sprayed; (SF): flushing






Organic Harbour Mud as Construction Material





Installation loaded geotextile

Sand installation (spraying)

Sand installation (flushing)







(O): originally; (B): backfilled; (SP): sprayed; (SF): flushing






Organic Harbour Mud as Construction Material





Installation loaded geotextile

Sand installation (spraying)

Installation of vertical drainage stripes







(O): originally; (B): backfilled; (SP): sprayed; (SF): flushing





Organic Harbour Mud as Construction Material

Precaution in design process

- Intensive geotechnical design in the design process by 3 experts.
- Wet assembly (sand): different parallel test methods for controlling of the layer thickness.
- Geotechnical measurement project
 - testing of the silt quality during the rearrangement.
 - permanent controlling of the silt strength and the silt consolidation after rearrangement.
- Geotechnical design being regularly updated (actual and forecast).
- Comparative geotechnical design from contractor/constructor





Organic Harbour Mud as Construction Material












Rearrangement of organic harbour mud









Organic Harbour Mud as Construction Material





















Organic Harbour Mud as Construction Material

Unexpected Surface distortion


- At the installation of the 5th sand layer during the spray coat method (D = 20 cm),
- "unexpected surface distortion" in the field,
- · circular bulges (silt),
- slipping of the sand layer in the area of the circular bulge,
- non failure of the geotextile,
- slowdown during approx. 10 days,
- big areas of construction site being affected almost at the same time.





Organic Harbour Mud as Construction Material












Unexpected Surface distortion









Organic Harbour Mud as Construction Material

Field enquiry

- > Analyzed parameter:
- · shear strength of the silt,
- homogeneity of the silt,
- thickness of the existing sand layer,
- position of the geotextile.



- "building blocks" of causes taken into consideration:
- (local) lower silt strength than assumed in design process,
- inevitable tolerance transgressions in the construction process,
- large density differences in the silt in connection with (partly) high salt contents,
- "mud flow" in the harbour during and prior construction phase,
- ground liquefactions during the construction process,
- impetus in the silt by gas (bulbs),
- strongly reduced permeability of the geotextile by hydrocarbons in a multiphase flowsystems,







Organic Harbour Mud as Construction Material





Thickness of sand layer (survey 11.11.2005); design thickness: 80 cm




Measured shear strength (11.11.2005)









 $c_u = 0.5 \text{ kN/m}^2$







Change of construction progress

- > Requirement:
- · safe construction and rapid progress of construction works,
- consideration of causal components,
- usability of the refilled area,
- limiting the additional expenses to the best economic level.



no further loading of the surface



lowering the pressure in the silt layer (gas/water).





Change of construction progress

- Design and construction implementation:
- installation of vertical drainage from floating equipment,
- installation of low pressure dewatering (BeauDrainS-method),
- intensive inspections on construction site (visual and measuring tech.),
- permanent update of the stability calculations on the basis of the field measurements and laboratory tests (actual and forecast; constructor and contractor parallel),
- application of the observation method according to DIN 1054,
- installation of sand; first dry setting with PistenBullies, later by flushing with "extreme lightweight equipment".






Organic Harbour Mud as Construction Material







setting and

assembly

BeauDrain-S












Organic Harbour Mud as Construction Material


























spring 2005

autumn 2006







Auch Chef-Ingenieur Woltering "würde es wieder so machen". Schließlich habe das innovative Verfahren Millionen gespart. Wäre ärts der Schlick nicht verbaut worden. hätte man ihn auf einer Bremer Deponie entsorgen müssen.

> den Weg weisen können. Iagen da aber noch night an den neuen Ka-

weserwarts. Au-

tofrachter, de-

Nach dem Bau einer Spundwund wurden weitere vier, fünf Meter aufgeschüttet.

Durüber kamen Textilmatten sich verschob und Wellen warf. und darsul noch 200000 Kublk-

meter Sand. Der konnte allerdings nicht planmäßig aufgebeacht werden, da der puddingartige Schlick

re Zusagen pünktlich ein". Laut BLG-Geschäftsführer Bernd Kupke bedeutet das allerdings: "Pünkt-

Zeitplanung," Umprünglich sei mit um bis gwilf Monaten weniger bnet worden. Dennoch gebe LG "keine Beschwerden -

e im Osthafen übergeben

Auch Chef-Ingenieur Woltering würde es wieder so machen" Schüellich habe das innovative Verfahren Millionen gespart. Wäre der Schlick nicht verbaut worden. afte man the auf einer Bromer Deponie entsorgen müssen. 24 Millionen Euro waren für den Bau rerenschlagt, so Rüdiger Staats, genaue Abrochmung stehe

Und halten wird das Pundament aus Schlick und Sand laut Wohnring besser als manche Fläche des Container-Terminal 1 - die seit den 70er Jahren um einen Meter obgesackt sei.

Bevor die Autos kommen, mass die BLG ihr neues Gelände noch asphaltieren. Ganz fertig sein soll es im Sommer. Ebenfalls im Sommer will Bremenports den Bau der neuen Kalserschleuse beginnen





Consequences for future "silt", projects.

- The disadvantageous influence factors like microbial and ground mechanical qualities of the silt should be more examined.
- Large density differences and cavities by gas formation must be taken into account on stability forecasts.
- Reconsideration of the method for the land reclamation / backfill with sands and optimizing the installation time for the vertical drainage.
- All used components should be tested before under conditions similar to the construction site as best as possible.
- The "restart of microbial processes" in the silt at the time of the rearrangement must be taken into account.





Organic Harbour Mud as Construction Material







